

SURVEY & ORIENTATION

MAR 29 2000

Approved by Menominee County  
Land Survey Remuneration  
Peer Group Under Act 345 Of

P.A. of 1990 On 10/1 1999  
Mr. Davis  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 35NR 27W E-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Sectional Subdivision by James H. Mullett - B.T.'s - Tamarack, 3" - N17°W - 11 lks.; Cedar, 5" - S51°W - 14 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. Nail in the centerline of a North - South County Road, in line with an ancient fence line to the East and a newer fence line to the West. The measurement 1/2 mile West is 2652.33 feet. The measurement 1/4 mile East to an ancient 1/16 fence is 1392.2 feet. LCRC No. 206, Book 4, by Ed Kazianka, documents that the position of this P.K. Nail was used along with the 1/16 fence and the distance between them doubled to establish the position of the SW Corner of Section 4. This makes the measurement 1/2 mile East 2784.4 feet, which is quite long, but fits well with long standing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N 16° E	74.99 feet	1 ft. E of power pole
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	East	31.52 feet	@ sign post
18" dia. White Ash	S 56° W	47.67 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N 27° W	69.13 feet	.65 ft. E of Anch pole
Metal Survey Sign Post			

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999

BK 6 Pg 102

RECEIVED FOR RECORD  
28 DEC 1999 3:56:09 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

