

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1999 On 10/11, 1999
Mc Davis RGS
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>35</u> N R <u>27</u> W | F-5 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

RECEIVED FOR RECORD
99 OCT 15 PM 1:42
PAGE # 26 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 6" - N34°W - 5 lks; Cedar, 6" - S21°E - 11 lks. All original evidence for this corner has been destroyed by county road improvements.
1990: L.C.R.C. No. 894 by William Lenca, RLS No. 26461. Set RR Spike in center of intersection of Co. Rds N-S-E-W. This position fits well with 1/16 corner to the East. TIES: Power Pole - N49°E - 65.63'; 5/8" x 24" Iron Rod/ID cap - S45°E - 45.94'; Cedar, 24" - S34°W - 64.70'; Chisel mark in W. end of S. culvert - N33°W - 56.18'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a Railroad spike the centerline of a 4 way county road intersection, along with the 4 ties described in L.C.R.C. No. 894 in part "A" above. Although the measurements the corners 1/2 mile East (2765.44') and 1/2 mile West (2619.20') do not fit well, this position fits with long standing lines of occupation, and has been used by local surveyors for several years, and is therefore accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- | | | | |
|---|-------|------------|------------------------|
| 16" dia. Tamarack | N45°E | 91.09 feet | Scr. NBT |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S43°E | 39.93 feet | 1' S. of Telephone Box |
| 24" dia. Cedar (Ex. B.T.) | S35°W | 64.70 feet | Scr. NBT |
| 7" dia. Cedar | N37°W | 87.86 feet | Scr. NBT |
| Metal Survey Sign Post | S43°E | 40.7 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 7, 1999