

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1999 On 10/11 1999  
Mac Davis RLS  
Chairman

For corners in  
MENOMINEE  
(County)

Located In: Corner Code #

1. Public Land Survey T35N R27W F-07  
T R  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R  
S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

BK. 6 Pg. 103

RECEIVED FOR RECORD  
28 DEC 1999 3:56:08 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	13	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on Nov. 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Sectional Subdivision by James H. Mullett - B.T.'s - Birch, 6" - S13°W - 10 lks.; Hemlock, 14" - N73°E - 23 lks. All original evidence for this corner has been destroyed county road improvements.
  - 1990: L.C.R.C. No. 894 (Bk 3) by William Lenca, RLS No. 26461 - Set 5/8" x 24" Iron in center of intersection of Co. Rds N - S & E - W. TIES: W. Pine, 5" - N65°E - 73.69'; PP - S50°E - 54.79'; Stop Sign - S70°W - 33.56'; W. Ash, 20" - N31°W - 50.94'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch diameter x 24 inch long iron rod in the centerline of a 4 way county road intersection. We also found the ties matching the corner location as described in L.C.R.C. No. 894, Book 3. This position fits well with measurements to corners 1/2 mile West (2672.05 feet) and 1/2 mile East (2673.45 feet), and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

9" dia. White Pine (Ex. B.T.)	N65°E	73.79 feet	Scr. NBT
5/8" x 24" Iron Rod/Ident. cap	S52°E	55.80 feet	1' East of Power Pole
5/8" x 24" Iron Rod/Ident. cap	S46°W	35.25 feet	1' East of Tel. Box
12" dia. White Ash (Ex. B.T.)	N39°W	51.02 feet	Scr. NBT
Metal Survey Sign Post	N44°E	46.9 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 17, 1999