

APR 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On 10/29 1998
William J. Wilson P.S.
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 35NR 27W	F-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORDING
98 NOV 16 AM 9:59
PAGE # 639 BK 5
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858
Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on June 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11						⊙							
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Elm, 15" - S38°E - 09 lks.; Cedar, 10" - N87°W - 25 lks. All original evidence for this corner has been destroyed by logging activities.
Terrain Call: Leave swamp 2.9 Chains West and 2.1 Chains East.
- 1984: L.C.R.C. Number 603 by George B. Wilson states, "FOUND ORIG. CED. B.T.; FOUND 1-1/2" dia. iron pipe 10.5' East. (not used)" Set 4" dia. Berntsen HDR Monument - TIES: Deep 1 set 2' North and 2' East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Berntsen HDR monument in a location as indicated in Land Corner Recordation Certificate Number 603 by George B. Wilson, RLS No. 17607. We also found remnants of an old cedar stump which is believed to have been an original bearing tree. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing HDR monument - stamped for corner location:

9" dia. Cedar	S76°E	26.65 feet	Scr. NBT
14" dia. Cedar	S34°W	14.50 feet	Scr. NBT
9" dia. Maple	N56°W	16.56 feet	Scr. NBT
1-1/2" dia. Iron Pipe	N75°E	10.9 feet	
Metal Survey Sign Post	North	1.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998

