

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code #
 T 35N R 27W G-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

Property Controlling in Section
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

Miscellaneous Property in Sec.
 S _____ T _____ R _____

Chairman
 PAGE # 225 BK 4
 BARBARA M. THOMPSON
 REGISTERED LAND SURVEYOR
 95 NOV - 8 AM 11:30
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca, in a field survey on Jul 12, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 8" - S32°E - 14 lks; Hemlock, 8" - N65°E - 21 lks. All original evidence has been destroyed by farming activities.
- 1994: LCRC No. 205 recorded in Book 4 of Corner Records by Edward Kazianka, RLS No. 14765 states that a 1" x 36" Iron Pipe was set in line with old fences East and South. New B.T.'s - 3" Iron Gate Post - N51°E - 1.50 feet; 3" Iron Gate Post - S35°E - 17.68 feet; W. Birch, 6" - N20°W - 13.98 feet.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1 inch diameter iron pipe in a location indicated by information in LCRC No. 205, Book 4. This corner falls in line with ancient fence lines running East and South from this location. The measurement from this corner to the Section Corner 1/2 mile North is 2502.84 feet compared to a GLO distance of 2508. The distance from this corner to the Section Corner 1/2 mile to the South is 2612.08 feet compared to a GLO distance of 2640. This corner position fits well with existing long standing occupation and is accepted as the best available evidence of the position of the original corner.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Sct 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:
 - Top of 3-1/2" dia. Iron Pipe (Gate Post) S87°E 17.82 feet
 - 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" South 47.78 feet
 - 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" West 23.74 feet
 - 8" dia. W. Birch N21°W 13.98 feet Scr. NBT
 - Carsonite Sign Post S20°W 1.5 feet

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 31, 1995
 Surveyor's Michigan License No. 26461

SURVEY & REMONUMENTATION