

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 10/16 19995
Mr. David RLS
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

<u>MENOMINEE</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

95 NOV - 8 AM 11:30
 RECEIVED FOR RECORDS
 PAGE # 228 224
 BARBARA JOHNSON
 REGISTRAR
 REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca in a field survey on Jul 18, 1995

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Sugar Maple, 10" - N49°E - 28 lks; Elm, 12" - S55°E - 25 lks. All original evidence has been destroyed by County Road Improvements.
- 1990: LCRC 890, Book 3 - recorded by William Lenca, RLS No. 26461 states that a railroad spike was found at intersection of county roads - WITNESSES - Nail in Anchor Pole - N45°E - 51.09'; Road Sign Post - S33°E - 46.33'; 24" Poplar - S49°W - 53.03'; 34" Poplar - N47°W - 51.30'.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a March 1995 survey of Section 10, we found a Railroad Spike and Witnesses in place as described in LCRC 890, Book 3 and as stated in part "A" above. The corner falls in the centerline of county roads running North - South and East - West from this location. This corner fits well with existing long standing occupation and is accepted as the best available evidence of the position of the original corner.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5" dia. Elm	S40°E	49.79 feet	Scr NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N26°E	53.21 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S32°W	46.33 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N47°W	46.54 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Recorded by William Lenca Date July 31, 1995
 Surveyor's Michigan License No. 26461

SURVEY & MONUMENTATION