

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/29 1998
James S. Wainwright P.S.
Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T 35NR 27W	G-09
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD
98 NOV 16 AM 10:00
PAGE # 645-285
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49958
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug. 18, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 12" - S38°W - 20 lks.; Hemlock, 14" - N84°E - 23 lks. All original evidence for this corner has been destroyed by county road improvements.
 - 1982: Certified Survey No. 297 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 27, T35N-R27W.
 - 1988: L.C.R.C. Number 804 by William Lenca states, "Set corner in line with county road centerlines East, West and South and in line with old fence to the North." Set 30" Alum. Mon./4" dia. Alum. cap stamped for corner location. TIES: Elm, 14" - N31°E - 52.20'; Power Pole - S42°W - 51.05'; Deep-1 Magnet - S28°E - 51.87'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found an aluminum monument with a 4" diameter aluminum cap in the centerline of county roads East - West - South and in line with an old fence to the North as indicated in Land Corner Recordation Certificate Number 804 by William Lenca, RLS No. 26461. This position fits well with measurements shown in Certified Survey No. 297, has been used in other surveys, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing aluminum monument and stamped it for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	North	31.71 feet	@ Sign Post
4" dia. Cedar	N54°E	81.05 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S44°E	47.34 feet	2' E. of Tel. Box
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S48°W	50.07 feet	1' E. of PP
Metal Survey Sign Post	North	32.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 21, 1998
Surveyor's Michigan License No. 26461



645