

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 10/1 1999  
Mel Davis RLS  
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> N <u>R</u> <u>27</u> W	<u>H-7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

BK. 6 Pg. 107  
RECEIVED FOR RECORD  
28 DEC 1999 3:56:09 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Sectional Subdivision by James H. Mullett - B.T.'s - Birch, 6" - S40°W - 09 lks.; Cedar, 10" - S77°E - 09 lks. All original evidence for this corner has been destroyed county road improvements.
- 1976: Recorded Plat of VIRGINIA SUBDIVISION by George B. Wilson, RLS No. 17607, shows the NE Corner of Section 22 and the East 1/16 Corner on the North Line of Section 22.
- 1988: L.C.R.C. No. 804 (Bk 3) by William Lenca, RLS No. 26461 - Set 5/8" x 24" Iron in location indicated by retracement of South Line of Section 15 T35N-R27W, as monumented by George B. Wilson, RLS 17607. TIES: PP - S52°E - 53.60'; W. Ash, 8" - S14°W - 80.50'; N. end of Culvert - N64°E - 38.25' to chisled cross.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch diameter iron rod in the center of an East - West County Road matching with the ties shown in L.C.R.C. No. 804, Book 3. This location was arrived at by using information contained in the recorded plat of VIRGINIA SUBDIVISION, recorded by George B. Wilson in 1976. The plat shows a tie from the NE Corner of Section 22 to the E1/16 Corner on the North Line. We projected this line West and doubled the distance between these corners to establish the N1/4 Corner of Section 22. This position has been used by local surveyors for more than 23 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

8" dia. Cedar	S 50° E	70.43 feet	Scr. NBT
8" dia. Elm	S 10° E	68.93 feet	Scr. NBT
9" dia. Elm	S 18° W	87.79 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	North	30.95 feet	@ sign post
Metal Survey Sign Post	North	31.60 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999