

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. 01-1990 On 10/29 1998
James J. Wain P.S.
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 35NR 27W

H-09

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, William Lenca, in a field survey on May 06, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECEIVED FOR RECORDING
98 NOV 16 AM 10:00
PAGE # 640, EXS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49958

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9							⊕					
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Sugar, 12" - S64°E - 10 lks.; Sugar, 4" - N35°W - 22 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1982: Certified Survey Number 297 by George B. Wilson, RLS No. 17607, shows this corner in relation to other corners in Section 27, T35N - R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. nail which we previously set from measurements shown in Certified Survey Number 297. This location falls in the centerline of county roads East - West - North. This position fits existing lines of occupation, has been used in other surveys, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N46°E	58.55 feet	@ Sign Post
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S36°E	41.82 feet	Nothing Near
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S41°W	43.83 feet	1' W. of P.P.
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N36°W	52.89 feet	1' E. of Rd. Sign
Metal Survey Sign Post	N46°E	59.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998