

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
 (County)

Located In: \_\_\_\_\_ Corner Code 77

1. Public Land Survey T 35N R 27W \_\_\_\_\_ I-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
 95 NOV - 8 AM 11:31  
 PAGE 236 BR 4  
 BARRINGTON  
 REGISTER OF DEEDS  
 MENOMINEE COUNTY  
 Register of Deeds Stamp & File Number

William Lenca in a field survey on July 18, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

1. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Sugar (Maple), 14" - S20°E - 17 lks; Sugar (Maple), 14" - N71°E - 32 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1980: L.C.R.C. No. 222 recorded by Edward Kazianka, RLS No. 14765, states that a 5/8" x 12" Re-rod was set in the center of county roads. TIES: 18" Elm - S42°E - 43.45'; 12" Maple - N32°E - 32.32'; Power Pole - N49°W - 38.68'; Power Pole - S41°W - 49.40'.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a April 1995 survey of Section 10, T35N-R27W, we recovered a 5/8" diameter x 12" iron re-rod in the centerline intersection of county roads running North - South and East - West. None of the corner ties mentioned in LCRC No. 222 were found. This corner position has been used consistently for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

20" dia. Elm	N25°E	85.30 feet	Scr NBT
Nail in Power Pole	S46°E	46.04 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S52°W	46.00 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N46°W	57.02 feet	
Metal Survey Sign Post	N46°W	57.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sept. 6, 1995  
 Surveyor's Michigan License No. 26461

