

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/11, 1999
Mc Davis RLS
Chairman

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35NR</u> <u>27W</u>	<u>I-8</u>
	T <u> </u> <u> </u>	<u> </u>
	T <u> </u> <u> </u>	<u> </u>
	T <u> </u> <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Bk. 6 Pg. 108

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct. 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Sectional Subdivision by James H. Mullett - B.T.'s - Cedar, 6" - S08°E - 08 lks.; Cedar, 4" - N84°W - 09 lks. All original evidence for this corner has been destroyed county road improvements.
- 1976: L.C.R.C. No. 149 (Bk 1) by Ewart Muller, RLS No. 15408 - Found 3/4" x 18" Iron pipe over a 3/4" x 18" iron shaft. 1980 TIES: Power Pole - S44°E - 40.70'; Power Pole - S43.5°W - 37.05'.
- 1980: Certified Survey No. 140 by Ewart Muller, RLS No. 15408 is tied to this corner. The corner monument is described as "Found 3/4" Iron Rod" - Witnesses: Power Pole - S44°E - 44.70'; Power Pole - S43.5°W - 37.05'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1987 survey in the City of Stephenson, we recovered a 3/4 inch diameter iron rod 18 inches long as described in L.C.R.C. No. 149. We replaced the iron with a W-1-B monument which was found in place in our 1999 remonumentation survey. This corner has been used by local surveyors for control in several surveys in this area, fits well with measurements to corners 1/2 mile North (2660.09 feet) and 1/2 mile South (2657.03 feet), and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing Berntsen W-1-B Monument 30" long with 4" dia. Alum. cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S 45° E	39.84 feet	1 ft. W of power pole
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S 40° W	40.20 feet	1 ft. W of power pole
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N 47° W	59.90 feet	@ sign post
Metal Survey Sign Post	N 47° W	60.30 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999

