

APR 06 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/29 1998  
James S. Warren P.S.  
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>I-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD  
90 DEC 14 PM 3:21  
PAGE # 670 BKS  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49886

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Mar. 30, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 15" - S86°E - 18 lks.; Sugar, 8" - S58°W - 20 lks. All original evidence for this corner has been destroyed by farming activities.
- 1982: Certified Survey Number 297 by George B. Wilson shows this corner in relation to other corners in Section 27, T35N-R27W.
- 1986: William Lenca field notes - Set County Monument in line with fences North - South and East. This position fits an existing East - West 1/16 fence to the South. TIES: Maple, 16" - S70°E - 85.15'; W. Birch, 11" - South - 106.55'; W. Birch, 4" - S70°W - 72.80'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4" x 5' Aluminum Rod / 3-1/4" Aluminum cap stamped for corner location in line with ancient fences North, South, and East. We also found two bearing trees (16" Maple and 4" White Birch) as indicated in William Lenca's field notes dated 1986. This position has been used in other surveys, fits existing lines of occupation and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long Aluminum Rod/3-1/4" dia. Alum. cap stamped for corner:

6" dia. White Birch (Ex.)	S70°W	72.80 feet	Scr. NBT
18" dia. Maple (Ex.)	S70°E	85.06 feet	Scr. NBT
4" dia. Balsam	S30°W	72.20 feet	Scr. NBT
8" dia. White Pine	N65°W	137.57 feet	Scr. NBT
Metal Survey Sign Post	North	0.9 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Apr. 08, 1998

