

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/29 1998  
James L. Lenca P.S.  
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>27</u> W	<u>I-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD  
93 DEC 14 PM 3:21  
CASE # 673 BKS  
SARASOTA CORPORATION  
REGISTER OF DEEDS  
MEMPHIS, TN 38103

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct., 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 18" - S06°E - 26 lks.; Cedar, 20" - N19°W - 10 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1986: L.C.R.C. Number 738 by William Lenca states, "Set Corner in center of East - West County Road in Line with old fences North and South." Set 5/8" x 24" Iron Pin / Ident. cap marked "MI. LS 26461/WI. LS 1569. TIES: W. Birch, 10" - N28°E - 82.73'; Cedar, 10" - S38°E - 37.39'; Balsam, 5" - S30°W - 25.72'; Power Pole - N63°W - 69.90'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered the 5/8" x 24" iron pin set as described in L.C.R.C. No. 738 in the centerline of an East - West County Road and in line with old fences running North and South. We also recovered the 4 witnesses as described above. The position of the corner monument fits well with Section Corners 1/2 mile North and 1/2 mile South, has been used as control for surveys in the area for at least 12 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

10" dia. Cedar	N50°E	64.45 feet	"X" cut in Upper & Lower blaze
10" dia. Cedar	S38°E	37.35 feet	"X" cut in Upper & Lower blaze
8" dia. Cedar	S60°W	69.74 feet	"X" cut in Upper & Lower blaze
7" dia. Cedar	N20°W	57.81 feet	"X" cut in Upper & Lower blaze
Carsonite Marker	South	30.2 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 29, 1998