

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/29 1998
Lawrence S. Wynn RS
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>34</u> N R <u>27</u> W	<u>I-01</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD
98 DEC 14 PM 3:20
PAGE # 668 B/C/S
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49835

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

(SAME AS CORNER I-13, T35N-R27W)

I, William Lenca, in a field survey on June 09, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey - Township Boundary - by H. Floyd - B.T.'s - Hemlock, 10" - N50°E - 46 lks.; Hemlock, 8" - N70°W - 19 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1848: Original Survey - Sectional Subdivision - by James H. Mullett - B.T.'s - Birch, 12" - S11°W - 16 lks.; Hemlock, 14" - S46°E - 34 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1963: M.D.O.T. Highway Plans show a 5/8" Iron Pin for this corner. - TIES: N.W. Cor. Pump Stand - S15°E - 36.62'; Maple, 20" - S40°W - 55.76'; P. Pole - N30°E - 18.22'. (These ties have been destroyed.)
- 1981: Certified Survey No. 235 by George B. Wilson shows a Cast Iron Monument Box at this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2" diameter iron rod in a square cast iron monument box per Certified Survey Number 235 by George B. Wilson. The ties shown on the 1963 Highway plats have been destroyed, however newer ties by M.D.O.T. as described in part "C", indicate that this is the corner position which they are using. The corner falls in the centerline of an East - West county road. This position has been consistently used by local surveyors for at least 35 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3-1/4" dia. Alum. cap stamped for corner location on existing 1/2" dia. iron rod in Monument Box:

MDOT Tag in Power Pole	N25°E	23.36 feet	
N.W. Corner of House Foundation	S23°E	88.85 feet	
MDOT Tag in Power Pole	S75°W	72.86 feet	
5/8" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N27°W	66.61 feet	1' S.E. of 10" Maple
Metal Survey Sign Post	N20°E	23.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca

Date Oct. 13, 1998

Surveyor's Michigan License No. 26461

