

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	Located In:	Corner Code
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	J-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
 95 NOV - 8 AM 11: 31
 PAGE # 338 BK 4
 BUREAU OF LAND SURVEY
 REGISTERED LAND SURVEYORS
 HEMLOCK, MICHIGAN 49830

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

(T36N-R27W - J-13)

William Lenca, in a field survey on Aug. 03, 1995,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law: established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd (Township Exterior) - B.T.'s - Hemlock, 8" - N32°E - 32 lks; Hemlock, 10" - N50°W - 21 lks. All original evidence has been destroyed by County Road improvements.
- 1903: PERRIZO'S ADDITION TO THE VILLAGE OF DAGGETT by Albert Hass, Surveyor, shows this corner as being 240 feet East of the East Line of the Plat, which is also the West Right of Way of the Chicago and Northwestern Railroad. The legend of the Plat describes this corner as a Cedar Post.
- 1976: Certified Survey No. 137 by Ewart Muller, RLS No. 15408, describes this corner as "Fnd Stockman Water Cap". TIES: Power Pole - N50°E - 65.6'; Power Pole - N50°W - 51.27'; NE Bolt on conc. slab - S20°W - 31.0'.
- 1980: Certified Survey No. 176 recorded by George B. Wilson, RLS No. 17607, shows this corner as it relates to Corners I-1 (NW Corner of Section 2) and Corner K-1 (NE Corner of Section 2). No description of the corner monument is given, and no description of corner evidence found and/or method applied in restoring or reestablishing corner.


In an August, 1995 survey of Section 2, T35N-R27W, we found a 3-1/2" dia. Metal cap in the centerline of County Road No. 358 (East - West), and in a location that matches with the record measurements in Certified Survey No. 176. The position of the cap also matches the distance West to the East Line of PERRIZO'S ADDITION TO THE VILLAGE OF DAGGETT also being the West Right of Way of the Chicago and Northwestern Railroad. We also located the 2 Power Poles used as ties in Certified Survey No. 137 and found that they fit with this corner. This position has been used consistently for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.

B. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2" dia. Iron Pipe/3-1/2" metal cap stamped for corner location:

P.K. Nail in Power Pole	N70°E	65.45 feet
NE Corner of Building Foundation	S56°E	72.01 feet
P.K. Nail in Power Pole	S54°W	94.11 feet
SE Corner of Brick Bldg.	N48°W	59.83 feet

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape.



Signed by William Lenca Date Sept. 06, 1995
 Surveyor's Michigan License No. 26461