

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On 10/11 1999
Me. Davis RLS
Chairman

For corners in SECTION

MENOMINEE

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--|------------|
| 1. Public Land Survey | T <u>35</u> NR <u>27</u> W | <u>J-5</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling
in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous
Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Bk. 6 Pg. 109
RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Sectional Subdivision by James H. Mullett - B.T.'s - Black Ash, 8" - N86°W - 2.94 lks.; Black Ash, 6" - S80°W - 2.8 lks. All original evidence for this corner has been destroyed by years of decay.
- 1896: Subd. of Section 11 by Justus Little shows measurements across the South Line of Section 11. These measurements are considerably short compared to present distances between existing monuments. The corner monument is not shown or described.
- 1980: L.C.R.C. No. 223 by Edward Kazianka, RLS No. 14765 - Accepted 1-1/4" iron pipe found at fence junction. TIES: Black Ash, 4" - N28°W - 7.85'; Maple Clump - S02°W - 17.62'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch diameter iron rod inside a 1-1/4 inch diameter iron pipe at an ancient fence corner, along with 2 witnesses as described in LCRC No. 223 (see part "A"). This corner has been accepted and used by local residents and surveyors for many years, fits well with a GLO call to the Little Cedar River 70 feet East, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

- | | | | |
|------------------------|---------|------------|----------|
| 12" W. Ash | N 80° E | 47.26 feet | Scr. NBT |
| 14" dia. Maple | S 05° E | 16.52 feet | Scr. NBT |
| 9" dia. Cedar | S 47° W | 46.04 feet | Scr. NBT |
| 5" W. Ash | N 35° W | 7.87 feet | Scr. NBT |
| Metal Survey Sign Post | North | .90 feet | |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999