

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/29, 1998  
Thomas J. Wenie, P.S.  
Chairman

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>MENOMINEE</u><br>(County)          | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>35N</u> R <u>27W</u> | <u>I-09</u>   |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |

RECEIVED FOR RECORD  
98 DEC 14 PM 3:21  
PAGE # 674 BKS  
SARAFRA NORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on May, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Beech, 5" - S28°W - 28 lks.; Beech, 7" - N38°W - 34 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1963: M.D.O.T. Highway Plans show this corner as a 1" Iron pin. TIES: Power Pole - N35°W - 29.97'; Apple, 8" - N50°E - 49.08'; Power Pole - S05°E - 31.50'.
- 1981: L.C.R.C. Number 327 by Edward Kazianka states, "3/4" Iron pin in Black-top road set by persons unknown." TIES: Power Pole - S10°E - 32.87'; Power Pole - S05°W - 32.30'; Power Pole - N33.5°W - 31.92'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

My field notes indicate that in a 1986 survey of Section 26, T35N-R27W, we recovered a 1 inch diameter iron rod in the centerline of an East - West County Road and in line with an ancient fence running South. We also recovered the witnesses as described in L.C.R.C. No. 327 described in Part "A", fitting the existing iron. We replaced the iron with a standard County Road Monument consisting of a Berntsen W-1-B Monument with a 4 inch diameter aluminum cap. In our 1998 remonumentation survey, we recovered the W-1-B Monument, and accepted its position as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing W-1-B Berntsen Monument 30" long with 4" dia. Alum. cap stamped for corner location:

|   |       |            |                    |
|---|-------|------------|--------------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N54°E | 66.61 feet | 1' W. of Stop Sign |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S09°W | 32.93 feet | @ Survey Sign Post |
| 8" dia. Cedar   | S57°W | 84.84 feet |                    |
| 10" dia. Cedar  | N09°E | 58.67 feet |                    |
| Metal Survey Sign Post  | S09°W | 33.5 feet  |                    |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 29, 1998

