

REGISTERED SURVEYOR & RE-ESTABLISHMENT

APR 06 1999

Approved \_\_\_\_\_ nee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/14, 1998  
James S. Wornie P.S.  
 Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

| <u>MENOMINEE</u><br>(County)          | Located In:             | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey                 | <u>T35N R 27W</u>       | <u>J-11</u>   |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |

RECEIVED FOR RECORD  
 98 DEC 14 PM 3:20  
 PAGE # 661 BKS  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Mar. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:  
 1848: Original Survey by James H. Mullett - B.T.'s - Beech, 4" - N71°W - 23 lks.; Beech, 4" - S71°E - 32 lks. All original evidence for this corner has been destroyed by county road improvements.  
 1989: Certified Survey Number 669 by William Lenca shows this corner in relation to other corners in Section 35, T35N-R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 My Field Notes from a 1988 Survey show that we found a 1" diameter Iron Pipe in the centerline of an East - West County road and in line with a fence running North. We took the following ties: Cedar, 8" - N55°W - 58.23'; W. Birch, 14" - S48°W - 77.75'. In our 1998 remonumentation survey, we recovered the 1" diameter iron pipe and 2 B.T.'s in place. We accepted the location of the existing corner monument as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:  

|   |       |            |                   |
|---|-------|------------|-------------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N71°E | 57.09 feet | 1' S. of 5" Cedar |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | South | 34.43 feet |                   |
| 10" dia. Cedar  | N55°W | 58.23 feet | Ex. B.T.          |
| 10" dia. Tamarack   | N11°W | 46.12 feet | Scr. NBT          |
| Metal Survey Sign Post  | South | 34.5 feet  |                   |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 13, 1998  
 Surveyor's Michigan License No. 26461

661