

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/11/99
Mr. Davis
Chairman

Bk 6 Pg. 112

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in

MENOMINEE
(County)

Located in:

Corner Code #

1. Public Land Survey

T 35NR 27W _____ K-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range; may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Sectional Subdivision by James H. Mullett - B.T.'s - Spruce, 10" - N56°W - 20 lks.; Spruce, 10" - S16°E - 45 lks. All original evidence for this corner has been destroyed by county road improvements.

1896: Subd. of Section 11 by Justus Little shows measurements to other corners from this corner. The corner monument is not shown or described. All measurements in this survey are very short compared to present measurements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We accepted a position for this corner which was in the centerline of the North - South County Road and at a single proportionate distance between the E1/4 Corner of Section 11 and the E1/4 Corner of Section 14. This position matches well with a GLO call to a stream 1 chain East, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

5" dia. Elm	N 25° E	50.29 feet	Scr. NBT
9" dia. Elm	S 85° E	45.78 feet	Scr. NBT
5" dia. Elm	S 50° W	50.05 feet	Scr. NBT
6" dia. Elm	N 67° W	28.00 feet	Scr. NBT
Metal Survey Sign Post	East	27.95 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 23, 1999