

APR 06 1998

P.A. Of 1990 On 10/29, 1998  
Terence J. Wainio, P.S.  
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>27</u> W	<u>K-10</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD  
 08 DEC 14 PM 3:20  
 PAGE # 664 BKS  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on June 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 12" - S47°E - 18 lks.; Hemlock, 8" - N31°W - 27 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1977: L.C.R.C. Number 164 by George B. Wilson states, "Found old iron fork, 19" long, 3/4" dia." Set Concrete Monument 4" square, 6" below pavement. Monument is 30" long with 1/2" dia. iron rod in center. (No Ties)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 4" square concrete monument with a 1/2" iron pin in a location as indicated in Land Corner Recordation Certificate Number 164 by George B. Wilson, RLS No. 17607. The corner falls in the centerline of county roads North - South and in line with ancient fences East - West. This position has been used consistently by local surveyors for at least 21 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Accepted existing 4" square concrete monument with 1/2" iron pin in center:
- |   |       |             |                          |
|---|-------|-------------|--------------------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N27°E | 61.02 feet  | 0.7' S.W. of Apple Clump |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N80°E | 27.20 feet  |                          |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S13°W | 142.65 feet | 0.5' E. of Power Pole    |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N62°W | 87.43 feet  | 1.1' S.E. of 12" Maple   |
| Metal Survey Sign Post  | N80°E | 27.8 feet   |                          |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
 Surveyor's Michigan License No. 26461

Date Oct. 21, 1998