

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In: Corner Code: L-3

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>35N</u> R <u>27W</u> | <u>L-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Chairman
95 NOV - 8 AM 11:32
RECEIVED FOR RECORD
PAGE 843 BK 4
BANKS & JOHNSON
REGISTERED PROFESSIONAL
SURVEYORS
MICHIGAN 1983

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on Aug. 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - N88°E - 17 lks, Black Ash, 4" - N05°W - 06 lks. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1985 survey of Section 1, T35N-R27W, we set a 1/2" dia. x 24" Iron Rod at the intersection of ancient fence lines running North, South and East from this location. In an August 1995 survey of said Section 1, we recovered the 1/2" dia. iron rod. We found that the measurement from this corner West to the SW Corner of Section 1 is 2629.81 feet. This matches reasonably well with the GLO distance of 2644.29 feet. We accepted the position of the existing 1/2" iron rod at the ancient fence corner as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

10" dia. Cedar	N09°W	24.36 feet	Scr NBT
12" dia. White Ash	S71°E	15.13 feet	Scr NBT
12" dia. Cedar	S09°E	12.31 feet	Scr NBT
10" dia. Cedar	N81°W	17.45 feet	Scr NBT
Metal Survey Sign Post	North	1.2 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sept. 06, 1995

Surveyor's Michigan License No. 26461

DEC 1 1995