

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/11/99
McL Davis RLS
Chairman

BK. 6 Pg. 117

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BRBARR MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49958

Register of Deeds Stamp & File Number

For corners in

MENOMINEE (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>27</u> W	<u>L-7</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Mar, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 12" - N71°E - 30 lks; Fir, 12" - N30°W - 30 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1900: Section Subd. by Albert Hass shows this corner as it relates to other corners in Section 24, 35/27 and describes the monument as "4 inch Cedar post formerly set in center of Road.
- 1987: Certified Survey No. 581 by William Lenca, RLS No. 26461 shows a tie to this corner. An unrecorded Corner Certificate in my files states "set P.K. in c/I Co. Rds N-S-E-W. TIES: Power Pole - N16°W - 95.03'; Power Pole - S54°W - 48.72'; W. Ash, 9" - N50°E - 28.88'; W. Ash, 12" - S59°E - 61.02'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a P.K. Nail in the centerline of county roads running North - South - East - West matching with the ties as described in part "A" above. The position of the P.K. Nail fits with Albert Hass' record measurements to corners 1/2 mile East and 1/2 mile West, fits with long standing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

10" dia. White Ash	N50°E	28.83 feet	Scr. NBT
14" dai. White Ash	S59°E	60.90 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S54°W	48.08 feet	0.7' N. of Power Pole
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N16°W	93.83 feet	1' S. of Power Pole
Metal Survey Sign Post			

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 7, 1999

