

REMONUMENTATION

APR 06 1999

SECTION

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/29 1998  
James J. Wain P.S.  
Chairman

### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
(County)

Located In:	Corner Code #
T35N R 27W	L-09
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
98 DEC 14 PM 3:20  
PAGE # 655 BK 5  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on May 06, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 4" - N57°W - 74 lks.; B. Ash, 8" - S57°E - 84 lks. All original evidence for this corner has been destroyed by county road improvements.  
Terrain Call: 1.9 Chains West leave marsh, 1.6 Chains East leave marsh and enter swamp.
- 1900: Survey by Albert Hass shows this corner as being a 4" Cedar post formerly set in center of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. nail in the centerline of county roads East, West, and South. This location fits closely with Albert Hass' measurements to corners 1/2 mile East and 1/2 mile West. The position also fits well with 1/16th fences 1/4 mile East and 1/4 mile West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

6" dia. White Ash	N47°E	95.03 feet	Scr. NBT
6" dia. White Ash	S39°E	73.42 feet	Scr. NBT
10" dia. White Ash	S51°W	77.91 feet	Scr. NBT
7" dia. White Ash	N16°W	64.69 feet	Scr. NBT
Metal Survey Sign Post	S49°W	50.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 05, 1998