

SURVEY & REMONUMENTATION

APR 06 1999

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. 011990 On 10/29 1998
James S. Winn P.S.
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION _____

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
98 DEC 14 PM 3:20
PAGE # 654 BK 5
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49953

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on June 09, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 8" - S68°E - 05 lks.; Tamarack, 8" - S10°W - 10 lks. All original evidence for this corner has been destroyed by county road improvements.

1994: Certified Survey Number 830 by William Lenca shows he set a 5/8" x 24" Iron Rod / 3-1/4" dia. Alum. cap at this corner. TIES: Cedar, 8" - S46°E - 89.04'; Cedar, 6" - S03°W - 55.29'; Elm, 6" - N24°W - 62.66'; Witness Marker - S61°W - 74.22'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 5/8" x 24" Iron Rod with a 3-1/4" cap and 3 existing bearing trees as indicated in Certified Survey Number 830 by William Lenca, RLS No. 26461. The corner is midway between section corners and falls in the centerline of county roads East - West - North, and in line with an old fence South. This position has been used in other surveys, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Monument Box over existing 5/8" x 24" Iron Rod/3-1/4" cap:

8" dia. Cedar	S46°E	89.04 feet	Scr. NBT
6" dia. Cedar	S03°W	55.29 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S61°W	74.22 feet	@ fence post
6" dia. Elm	N24°W	62.66 feet	Scr. NBT
Metal Survey Sign Post	South	33.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998



654