

SURVEY & REVISION INFORMATION

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/28 1999
McDavin RLS
Chairman

For corners in SECTION

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T 35NR 27W	M-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

BK. 6 Pg. 89
RECEIVED FOR RECCRD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER A-8, T35N-R26W

I, William Lenca, in a field survey on Nov., 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Twp. Boundary by H. Floyd - B.T.'s - Y. Birch, 22" - S50°W - 15 lks; Hemlock, 10" - N70°W - 18 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1900: Survey by Albert Hass, County Surveyor, shows this corner as it relates to other corners in Section 24, T35N-R27W. The corner monument is described as "3 inch Cedar Post formerly set in center of Road".
- 1980: LCRC No. 262 by Gerald Carlson, RLS No. 24589 - Set P.K. Nail & Tab in c/l 4 way Road Int. TIES: P.K. Nail/Tab in T. Pole - S46°E - 47.25'; 4" Aspen - N60°W - 69.30'; P. Pole - N43°E - 44.35'.
- 1990: LCRC No. 890 by William Lenca, RLS No. 26461 - Found P.K. Nail/washer in c/l C.R. E-W-S. TIES: Nail in PP - N43°E, 44.34'; Nail in Anchor Pole - S42°E - 47.23'; Nail in PP - S44°W - 49.10'; Nail in 8" Poplar - N57°W - 69.18'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a P.K. nail with a bronze washer in the centerline of County Roads running East - West and South and in line with the centerline of an old lane (former county road) running North. We also found the ties as described in LCRC No. 262 (see part "A"). This corner position has been used as control by local surveyors for at least 19 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

Ex. Nail/washer in Power Pole	N43°E	44.35 feet	
Ex. Nail/washer in Anchor Pole	S46°E	47.25 feet	
Ex. Nail/washer in Power Pole	S41°W	49.11 feet	
6" dia. White Ash	N30°W	61.84 feet	Scr. NBT
Metal Survey Sign Post	S37°W	39.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 23, 1999

