

APR 06 1999

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/29 1998  
Terence J. Winni P.S.  
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T35N R 27W M-12

T R

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

(SAME AS CORNER A-12, T35N-R26W.)

I, William Lenca, in a field survey on Oct. 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - Cedar, 6" - S80°W - 15 lks.; Spruce, 8" - N20°W - 08 lks. All original evidence for this corner has been destroyed by logging activities.
- 1994: Certified Survey Number 830 by William Lenca indicates he set a 2-1/2" x 30" Bernsen Monument / 3-1/4" cap at this corner. TIES: W. Ash, 5" - N38°E - 15.59'; W. Ash, 9" - S40°E - 27.13'; Maple, 9" - S48°W - 28.88'; W. Ash, 24" - N47°W - 28.89'; Carsonite Marker - S56°E - 2.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 2-1/2" diameter aluminum pipe with a 3-1/4 inch diameter aluminum cap and 4 B.T.'s as described in part A above. The corner falls at the intersection of ancient fences running East - West and North. This location fits well with measurements to corners 1/2 mile North and 1/2 mile South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

5" dia. White Ash	N38°W	15.59 feet	Scr. NBT
9" dia. White Ash	S40°E	27.13 feet	Scr. NBT
9" dia. Maple	S48°W	28.88 feet	Scr. NBT
24" dia. White Ash	N47°W	28.89 feet	Scr. NBT
Carsonite Marker	S56°E	2.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 29, 1998

RECEIVED FOR RECORD  
98 DEC 14 PM 3:20  
PAGE# 659 BK 5  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858  
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



659