

SURVEY
RECORDATION

APR 06 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
PA 061290 On 10/29 1998
James J. Worrie P.S.
Chairman

For corners in

MENOMINEE

(County)

Located in:

Corner Code #

1. Public Land Survey

T34N R 27W

M-01

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims
(SAME AS CORNER M-13, T35N-R27W; A-13, T35N-R26W; A-01, T34N-R26W.)

I, William Lenca, in a field survey on June 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by H. Floyd - B.T.'s - Tamarack, 10" - N63°W - 26 lks.; Cedar, 14" - N37°E - 15 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set this corner in the centerline of an East - West county road and in line with an old fence to the South. This position makes the quarter corner to the West very nearly midway between section corners and fits closely with the GLO measurement to the 1/4 Corner 1/2 mile East, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"
4" dia. Elm
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"
6" dia. Double Elm (Left tree)
Metal Survey Sign Post

N40°E 29.63 feet
N73°E 80.98 feet
South 30.58 feet
N56°W 48.89 feet
South 31.6 feet

1' E. of 7" Poplar
Scr. NBT
@ Sign Post
Scr. NBT

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998

RECEIVED FOR RECORD
98 DEC 14 PM 3:20
PAGE # 660
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

