

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 N. R. 28-29 W


Menominee COUNTY

DESCRIPTION OF CORNER Section Corners common to Sections 30, 31, 25 and 36

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8-29-62

WITNESSES TO CORNER..... NBT's: 14" Red Oak S 42° W 86 links



(S 36 NBT)

14" Twin Red Oak S 64° E 73 links
(NBT)

5" Red Oak N 35° W 20½ links
(S 25 NBT)

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one W. Pine stump bottom bearing S 17° W 15 links. Distance East and South to marsh is good; distance to corners 1 mile East and West good.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-22-63
REGISTERED LAND SURVEYOR
Billy D. Buckler