

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 N. R. 28 W


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 31 and 32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-18-62

WITNESSES TO CORNER..... NBT's: 8" Cedar (1/2 S NBT) S 10° W 65 links



CIRCLE CORNER REGISTERED

8" Twin Cedar (1/2 S NBT) S 58° E 74 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed facing a Pine stump which is bearing S 50° E 18 links. Stump appears to have a lower face and notch cut when the tree was green.

Record bearing is S 17° E 18 links.

Corner lies 12 links North of a point midway between Section Corners and also is on a straight line between corners.

I believe there is an error in recording the bearing of the B.T.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-22-63
REGISTERED LAND SURVEYOR
Billy D. Buckler