

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 NR. 28 W.

Menominee

COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sec.'s 3-10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" Cedar	S 43° E	41½ links
	Marked "1/4 S NBT"	
6" Cedar	S 54° W	27 links
	"1/4 S NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from one cedar B.T. in good condition, bearing S 45° W 22 links.

Cedar post in place; other B.T. has been washed into stream.

1/4 corner lies on south bank of stream.

1/4 corner found by Forestry Division Survey Crew while making a partial re-survey of this area.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 4/16/57
REGISTERED LAND SURVEYOR