

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 NR. 28 W.

Menominee

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 4-5-8-9

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	7" Red Oak	N 85° W	45 links
	Marked	"S5 NBT"	
	10" Red Oak	S 53° W	45 links
	Marked	"S8 NBT"	
	8" Red Oak	S 22° E	31 links
	Marked	"S9 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from two Y. Pine B.T.s'

Found notch on stump bearing S 42° E 93 links and burned stump bottom N 29° W 56 links.

Position checks with corners in all four directions.

No evidence of use.

Corner found by Forestry Division Survey Crew while making a re-survey of this township.

SURVEYORS SEAL

SIGNED Billy D. Buchler DATE 4/16/57  
REGISTERED LAND SURVEYOR