

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 NR. 28 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 5-6-7-8

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Red Oak	N 87° W	31½ links
	Marked "S 6 NBT"	
5" Red Oak	S 44° W	36 links
	Marked "S 7 NBT"	
6" Red Oak	S 82° E	52½ links
	Marked "S 8 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from two probable B.Ts.

Y. Pine	N 57° W	143 links
W. Pine	S 71° E	316 links

Stumps both badly burned.

Distance checks very close to good corners, one mile east and one mile north.

No evidence of use in vicinity.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 5/10/57
REGISTERED LAND SURVEYOR