

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*MENOMINEE*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 35 N. 28 W. S., R.	K-1, J-1
2. PROPERTY CONTROLL- ING IN SECTION.....	2 T. 35 N. 28 E. S., R. W.	1
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. E. S., R. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 5, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-1 - N.E. Sec. Cor. of Sec. 2; wood post - Beach 8" - N22°W - 10 Lks.; Maple 6" - N46°E - 27 Lks.; W. Pine 14" - S15°E - 07 Lks.; W. Pine 14" - S54°W - 37 Lks.
- J-1 - North 1/4 Cor. of Sec. 2; wood post - W. Pine 24" - N71°W - 44 Lks.; W. Pine 36" - N62°E - 05 Lks.
- 1 - W. 1/16 Cor. on the North Sec. line of Sec. 2; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-1 - Set from stump of S.E. - O.B.T. axe hack marks on stump. (16" W.P. stump - S15°E - 4.6'). Falls in line with very old fence North. Notes of original Gov't survey in 1848 state "73.50 trail E. N.E.." A trail falls in that exact position from this corner now (on North line of Sec. 1).
- J-1 - Set M.P.O.L. between the N.E. & N.W. Sec. Cors. of Sec. 2. Several W.P. strips in the area but too rotten & burned to show marks and none in proper relationship to each other to fit the G.L.O. record for O.B.T.S.
- 1 - Set M.P.O.L. between the North 1/4 Cor. and the N.W. Sec. Cor. of Sec. 2.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- J-1 - D.N.R. Mon.; 4" Oak - N17°W - 17.35'; 5" Maple - N14°E - 10.85'; 5" Maple - S71°E - 22.8'; Tw. 5" Maple - S71°W - 28.6'.
- K-1 - D.N.R. Mon.; 22" W. Pine - N22°W - 63.95'; 16" W. Pine - S62°E - 128.1'; 7" W. Pine - S71°W - 45.6'; 4" W. Pine - N15°E - 17.6'.
- 1 - D.N.R. Mon.; Nail & brass tag in Cor. fence post - N28°E - 57.8'; nail & brass tag in Cor. fence post - S71°E - 106.2'; N.E. Cor. Hse. Fdtion - South - 160.55'; N.W. Cor. Hse Fdtion - S9°W - 164.1'.

SIGNED BY

*David B. Babbitt*

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: