

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>28W</u>	<u>I-8, I-9, H-9.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 6/7/88, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-8. E 1/4 corner of Section 22. Wood post 1852. W. pine 18, N44E, 58 lks.  
 W. pine 10, S35W, 81 lks.

I-9. SE section corner of Section 22. Wood post 1852. Cedar 12, N41W, 19 lks.  
 Cedar 10, S65E, 58 lks.

H-9. S 1/4 corner Section 22. Wood post 1852. Tam. 10", N27W, 30 lks.  
 Tam. 14", S56E, 27 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-8. Set in  $\oint$  of road south and in line with very old farm fence east. Mea. north and south to section corners fits well.

I-9. Set in  $\oint$  of roads in N-S-E&W. Fits occupied lines in all four directions. OBT's destroyed by road construction.

H-9. Set in  $\oint$  of E-W blacktop road and equal distance from the SE and SW section corners of Section 22. 2631.36 ft. each way.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-8. DNR Monument.	I-9. Menominee Co. Monument	H-9. Menominee Co. Monument
9" r.pine, N35E, 13.9'	5" tamarack, N47E, 81.35'	8" tamarack, N11W, 52.4'
11" r.pine, S54E, 35.3'	sign post S40E, 33.2'	9" cedar, N25E, 58.2'
7" j.pine, S53W, 41.1'	5" cedar, S45W, 83.6'	4" tamarack, S10E, 53.8'
4" w.pine, N22W, 34.3'	3" cedar, N52W, 108.2'	8" tamarack, S29W, 63.0'

Signed by David B. Babbitt

Date 9-29-88

Surveyor's Michigan License No. 21558