

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Menominee
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|------------------|
| 1. Public Land Survey | T <u>35N</u> R <u>28W</u> | <u>B-1, B-2.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 9/24/86, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-1. N 1/4 corner of Section 6.
 Wood post. September 3, 1852.
 Hemlock 14", N65E, 5 Lks.
 Hemlock 18", S74W, 27 Lks.
- B-2. Center of Section 6. No center of Section 6 on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-1. Set by single proportion between the Menominee River M.C. west and the NE section corner of Section 6 to the east.
- B-2. Set at the intersection of the N-S and E-W 1/4 lines of Section 6. There is a sq. cedar post and the corner of a single strand wire fence N85W, 36' from this point but I could find no record of its origin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------|----------------------------|
| B-1. DNR Monument | B-2. DNR Monument |
| 7" Basswood, S42W, 31.0' | 5" Maple, N7E, 32.8' |
| 8" Basswood, N88W, 40.3' | 5" Maple, S34E, 13.0' |
| 12" Basswood, N40W, 47.5' | tw. 6" Maples, S48W, 37.3' |
| 6" Oak, N05E, 42.4' | 7" Oak, N47W, 47.9' |

Signed by David B. Babbitt
 Surveyor's Michigan License No. _____ RLS 21558

Date 1-27-87