

2  
PFB

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Menominee  
(County)

Located In:

Corner Code #

- |                                    |                           |                       |
|------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey              | T <u>35N</u> R <u>28W</u> | <u>D-7, C-9, D-9.</u> |
|                                    | T _____ R _____           | _____                 |
|                                    | T _____ R _____           | _____                 |
|                                    | T _____ R _____           | _____                 |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____                 |
|                                    | S _____ T _____ R _____   | _____                 |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____                 |
|                                    | S _____ T _____ R _____   | _____                 |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, David Babbitt, in a field survey on 10/10, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- D-7. N 1/4 corner of Section 20. Wood post, 1852. Balm of Gilead 5 N60W, 6 lks.  
" 6 S15E, 14 lks.
- C-9. SW section corner of Section 20. Position indicated on drawing by R. Olson drawn in 1949 but no description of corner monument or witnesses.
- D-9. S 1/4 corner of Section 20. Wood post, Sept. 1852. Tam. 10, N61W, 14 lks.  
Cedar 20, S71E, 39 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-7. Set MPOL between the NW and NE section corners of Section 20. Corner falls on the north side of Shakey River.
- C-9. Set in E of E-W blacktop road by retracing R. Olson's 1949 survey. Falls nearly in line with old fence line running south from the road.
- D-9. Set MPOL between the SE and SW section corners of Section 20. OBT's would fall in roadway. Monument set flush with blacktop.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                              |                        |                             |
|------------------------------|------------------------|-----------------------------|
| D-7. 1" pipe w/DNR plug cap. | C-9. DNR Monument      | D-9. Menominee Co. Monument |
| 10" cedar, N73E, 22.05'      | 8" j.pine, S10W, 48.8' | 4" cedar, S30E, 77.9'       |
| 8" b.ash, S54E, 23.1'        | 10" oak, N5E, 37.0'    | 6" cedar, S44W, 75.3'       |
| 12" b.ash, S70W, 25.45'      | 14" oak, S50E, 94.9'   | 8" cedar, N7E, 53.2'        |
| 10" cedar, N41W, 54.9'       | 13" oak, N56W, 73.0'   | 10" cedar, N44E, 67.1'      |

Signed by David B. Babbitt Date 10-17-88  
Surveyor's Michigan License No. 21558