

OK  
PFB

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <del>≠</del>
1. Public Land Survey	T <u>35N</u> R <u>28W</u>	<u>A-9.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>35N</u> R <u>28W</u>	<u>15, 10,</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David Babbitt, in a field survey on 7/13, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 15. W. 1/16 on the south section line of Section 19. No previous record.
- 10. S. 1/16 corner on the west section line of Section 19. Iron corner. R. Olson, 1949. In clearing, no witnesses. Set MPOL.
- A-9. SW section corner of Section 19. Iron shown on survey drawing by R. Olson, 1949 and one by Geo. Wilson dated 1974, no witnesses shown on either drawing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 15. Set by single proportion to the original survey record between the south 1/4 corner and the SW section corner of Section 19.
- 10. Set MPOL between the west 1/4 corner and the SW section corner of Section 19. Mon. falls beside a section of steel fence post driven in.
- A-9. Found 3/4" pipe with metal plug buried in the centerline of E-W blacktop road. Fits description on a survey by R. Olson dated 1949 and certified Survey #30 by George B. Wilson RLS #17607, dated July 24, 1974. Set aluminum monument furnished by the Menominee County Road Commission in place of the found pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                         |                          |  |
|-------------------------|--------------------------|--|
| 15. DNR Monument        | 10. DNR Monument.        | A-9. Adjustable alum. mon. (Men.Co. Monu.) |
| 22" r.pine, N47W, 67.6' | 6" j.pine, N12E, 106.6'  |  |
| 9" oak, N36E, 49.7'     | 4" cherry, N47E, 60.1'   | 14" oak, S57E, 108.05'                     |
| 15" oak, S40E, 79.1'    | 10" j.pine, S19E, 45.05' | 8" oak, S28W, 75.7'                        |
| 11" oak, S19W, 60.8'    | 5" j.pine, S33W, 50.3'   | 12" oak, N45W, 57.8'                       |
|                         |                          | 7" oak, N36E, 59.35'                       |

Signed by David B. Babbitt Date 1-26-89  
Surveyor's Michigan License No. 21558