

OK
PRB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Menominee
(County)

Located In:

Corner Code #/

- 1. Public Land Survey T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S 19 T 35N R 28W 11.
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
6													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 10/10, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 11. SW 1/16 corner of Section 19. Iron corner, R. Olson, 1949.
10" oak, N30E, 15.6'
14" oak, S10E, 35.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11. Set at the computed center of the SW 1/4 of Section 19 by closed traverse. Mr. Olson's "iron corner: is nearby but was not accepted because, according to his drawing it was not set by proper section subdivision procedures. Proper location of the 1/16 corners in the west 1/2 of Section 19 present an unusual situation in that the NW section corner falls in a lake and the north section line was not completely measured in the original gov't. survey. By examining the acreages shown for the NW 1/4 of the SW 1/4 and the SW 1/4 of the SW 1/4 on the official twp. plat map of the original survey for T35N, R28W, it was determined that said acreages were based on a measurement for the north section line of Section 19 which was equal to a mean of the record measurement for the south section line of Section 19 and the north section line of Section 18. The position of this 1/16 corner was therefore computed based on said mean distance as the "record" measurement for the north section line of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 11. 1" pipe w/DNR yellow plastic plug cap.
8" j.pine, N10E, 20.6'
7" j.pine, S51E, 9.5'
10" oak, S21W, 44.8'
12" oak, N52W, 47.3'

Signed by David B. Babbitt Date 1-26-89
Surveyor's Michigan License No. 21558