

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Manominee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 35N R 28W	B-9.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, David B. Babbitt, in a field survey on 10/10/88, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-9. S1/4 corner of Section 19. Wood post, 1852. Spruce pine 12, N18W, 169 lks.  
 Y. pine 14, S77E, 82 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9. Set in  $\frac{1}{2}$  of E-W blacktop road for N-S position and distance proportioned to the original survey record. Considerations concerning the south 1/4 corner of Section 19, T35N, R28W.

1) Robert Olson RLS #10700, in 1949, set a number of corners in and around Section 19 and made a survey drawing showing distances from corner to corner but no bearings on the same. He does not, however, show anything on the south section line except the SW section corner and the drawing indicates but, does not state, that the south section line is on the  $\frac{1}{2}$  of an E-W road marked "Road to Stephenson". The drawing does, however, show "iron corner" for the south 1/16 corner and several other points in the south 1/2 of Section 19. Said south 1/16 corner does, in effect, create a position for the south 1/4 corner of Section 19. (continued on back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9. DNR Monument.  
 7" j.pine, N1E, 70.25'  
 14" oak, N65E, 69.7'  
 7" r.pine, S50E, 56.6'  
 9" r.pine, S2W, 36.1'

Signed by David B. Babbitt Date 1-26-89

Surveyor's Michigan License No. 21558