

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County) Located In: Corner Code //
1. Public Land Survey T 35N R 28W H-3
2. Property Controlling in Section S 10 T 35N R 28W 1, 1A, 1B
3. Miscellaneous Property in Sec. S T R
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. Section 10 is marked in the grid.

I, Paul R. Bressette in a field survey on October 18, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 3 Quarter Corner common to Sections 3 and 10 1957: Billy D. Buckler, RLS, set 1" pipe with 4" brass cap witnessed by: 8" Cedar S4PE 41.5 links; 6" cedar S54PW 27 links.
1 West one-sixteenth Corner common to Sections 3 and 10. Not set in original survey, no evidence of subsequent establishment.
1A One sixty-fourth corner east of the Northwest corner of Section 10. Not set in original survey, no evidence subsequent establishment.
1B One sixty-fourth corner west of the Quarter Corner common to Sections 3 and 10. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 3 Found two witnesses set by Buckler and stump of original bearing tree. No evidence of monument. Reset new DNR monument and witnessed.

Corner position established mid-point and on-line between the Northwest and North Quarter corner of Section 10. Corner falls north of the centerline of county road.

- A Corner position established mid-point and on-line between the West one-sixteenth Corner common to Sections 3 and 10 and the Section Corner common to Sections 3, 4, 9 and 10. Corner falls north of centerline of county road and in line with a fence south.

- B Corner position established mid-point and on-line between the West One-sixteenth and One Quarter Corners common to Sections 3 and 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with columns for H-3 DNR Mon., 1 DNR Mon., 1A 1" iron pipe w/plastic plug, and 1B 1" iron pipe w/plastic plug. Rows list various trees and distances.

Old NBTs



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date December 21, 1993