

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mike Evans RLS
Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey T35N R 28W C-7
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

RECORDED FOR RECORD
97 JUL 23 PM 3:34
FILE # 193 RLS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49853
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Apr. 03, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pinc, 22" - N44°E - 103 lks.; W. Pinc, 24" - S52°W - 41 lks. All original evidence for this corner has been destroyed by fire.
 - 1949: Park Survey by Robert Olsen states: "squared post used in 1931 was considered true corner previous". B.T.'s: 18" Norway Pinc - N15°W - 16.8'; 12" N. Pinc - N45°E - 12.9'.
 - 1961: Subd. of Section 18 by Dean Delamater indicates a monument at this location with ties to other corners. The monument is not described, but the map symbol is identical to other symbols described as "T" iron. No B.T.'s are given.
 - 1991: CERTIFIED SURVEY No. 769 by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 18.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1997 survey of Section 18, we recovered a "T" iron with a 1" diameter metal cap marked DELAMATER/MUSCHELL, ENGINEERS/SURVEYORS, CHEBOYGAN MICH., with the stumps of Robert Olsen's B.T.'s (described in part A above) still visible. This corner has been accepted by local surveyors for over 65 years, and is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner. Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location over existing "T" iron:
- | | | | |
|------------------------|-------|------------|----------|
| 12" dia. Oak | N06°W | 35.77 feet | Scr. NBT |
| 16" dia. Jack Pine | N76°E | 21.32 feet | Scr. NBT |
| 12" dia. Oak | South | 34.77 feet | Scr. NBT |
| 11" dia. Oak | S70°W | 15.67 feet | Scr. NBT |
| Metal Survey Sign Post | North | 0.9 feet | |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Apr. 07, 1997
Surveyor's Michigan License No. 26461

COMMISSION
REMONUMENTATION

DEC 28 1997

COMMISSION

193