

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/28, 1999
McL...
Chairman

Bk 6 Pg. 58

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>35NR</u> <u>28W</u>	<u>E-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. , Recorded Plat
5. Private Claims

I, William Lenca, in a field survey on Nov., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Aspen, 6" - N56°W - 14 lks.; Aspen, 6" - S47°E - 41 lks. All original evidence for this corner has been destroyed by county road improvements.
Terrain Call: 2.65 Chains North leave thickets - foot of ridge.
- 1989: L.C.R.C. No. 858 by William Lenca states, "Set corner in centerline of N-S County Road and in line with old fence line to the West." Set 5/8" x 24" Iron Rod / Ident. cap. TIES: Oak, 14" - N73°E - 52.92'; Power Pole - S10°E - 107.52'; Basswood, 20" - S34°W - 49.68'; Aspen, 8" - N37°W - 67.04'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch x 24 inch iron re-rod in the centerline of a North - South gravel surface County Road, in line with an old fence running West, in a location matching the ties described in LCRC No. 858 (see part "A"). This corner position fits well with existing lines of occupation and with measurements to corners 1/2 mile North (2640.01 feet) and 1/2 mile South (2637.53 feet), and is accepted as the best available evidence of the position of the original corner. (Note: Small differences in measurements to B.T.'s are due to the fact that old nails have been overgrown and new nails placed in the tree.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

6" dia. White Pine	N18°E	88.05 feet	Scr. NBT
16" dia. Oak ex. BT	N73°E	53.00 feet	Scr. NBT
8" dia. Balsam	S65°E	75.60 feet	Scr. NBT
20" dia. Basswood	S34°W	49.68 feet	Ex. BT
Metal Survey Sign Post	East	25.45 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 3, 1999