

APR 06 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/30, 1998

Med Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T5N R 28W</u>	<u>I-09</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD
99 JAN -6 AM 8:52
PAGE # 702 BKS-
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Sept. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 12" - N41°W - 19 lks.; Cedar, 10" - S65°E - 58 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1988: L.C.R.C. Number 834 by David B. Babbitt, RLS 21558, states: "Set in centerline of roads in N-S-E & W. Fits occupied lines in all four directions. OBT's destroyed by road construction." Set Menominee Co. Monument. TIES: Tamarack, 5" - N47°E - 81.35'; Sign Post - S40°E - 33.2'; Cedar, 5" - S45°W - 83.6'; Cedar, 3" - N52°W - 108.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Berntsen W-1-B monument (30 inch long cast aluminum marker with 4 inch diameter aluminum cap) in the centerline of county roads North, South, East, and West and 4 witnesses as described in Land Corner Recordation Certificate Number 834. This corner location has been accepted and used by local surveyors for over 10 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing W-1-B monument for corner location:

7" dia. Tamarack	N47°E	81.49 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S31°E	35.64 feet	1' E. of Stop Sign
7" dia. Cedar	S45°W	83.14 feet	Scr. NBT
5" dia. Cedar	N52°W	108.27 feet	Scr. NBT
Metal Survey Sign Post	N35°W	44.3 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 18, 1998