

APR 06 1999

P.A. of 1990 On 12/30 1998

Mr. Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T 35N R 28W	K-09
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

RECEIVED FOR RECORD
99 JAN -6 AM 8:51
PAGE # 698 JK5
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49850

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, William Lenca, in a field survey on Oct. 06, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pine, 12" - N37°W - 52 lks.; W. Pine, 12" - S64°E - 18 lks. All original evidence for this corner has been destroyed by county road improvements.
 - 1989: Certified Survey Number 663 by William Lenca, RLS 26461, shows this corner in relation to other corners in Section 24, T35N - R28W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. nail in the centerline of an East - West county road and in line with an ancient fence to the North. This position fits well with measurements to corners 1/2 mile North, South, East and West, and with a G.L.O. terrain call to a stream 2.05 chains West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:
- | | | | |
|---|-------|------------|----------------------|
| 10" dia. White Ash | N38°E | 62.19 feet | "X" cut in blaze |
| 6" dia. Maple | S36°E | 65.23 feet | "X" cut in blaze |
| 5" dia. Maple | S38°W | 82.42 feet | "X" cut in blaze |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N50°W | 70.31 feet | 1' S.E. of 5" Poplar |
| Metal Survey Sign Post | South | 42.3 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 18, 1998

698