

APR 06 1999

Approved by Menominee County Land Survey Remuneration Peer Group Under Act 345 Of P.A. Of 1990 On 12/30 1998
Mc Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35NR</u> <u>28W</u>	<u>L-09</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

99 JAN -6 AM 8:51
RECEIVED FOR RECORD
PAGE # 695
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct. 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pine, 24" - N31°W - 30 lks.; W. Pine, 12" - S42°E - 44 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1989: L.C.R.C. Number 851 by William Lenca, RLS No. 26461, states: "Set corner in line with County Road E-W and in line with an old fence line to the south." - Set Railroad Spike - TIES: W. Pine, 20" - N37°W - 63.65'; W. Ash, 8" - N03°W - 48.98'; Poplar, 8" - N52°E - 44.10'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a railroad spike in a location as indicated in Land Corner Recordation Certificate Number 851 by William Lenca, RLS No. 26461. This corner falls in the centerline of an East - West county road and in line with ancient fences North - South. This location has been used in previous surveys, fits well with measurements to corners 1/2 mile East and 1/2 mile West, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N50°E	42.56 feet	1' W. of 10" Poplar
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	South	27.98 feet	@ Carsonite
14" dia. White Pine	N36°W	63.58 feet	"X" in upper & lower
10" dia. Elm	N05°W	48.95 feet	"X" in upper & lower
Carsonite Survey Marker	South	28.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 22, 1998

