

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 35 N.R. 29 W


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 25 and 36

CORNER MONUMENT 1" Pipe with 1/4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9-18-62

WITNESSES TO CORNER..... NBT's: 7" Red Oak (1/4 S NBT) N 83° E 21 links



7" Red Oak (1/4 S NBT) S 33° W 50 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies 1 chain South of Road.

This corner re-established midway and on line between two Section Corners.

No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-22-63  
REGISTERED LAND SURVEYOR  
Billy D. Buckler