

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 .. NR. 29 W ..

Menominee .. COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec. 's 34-35 ..

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap ..

WITNESSES TO CORNER 12" Red Pine .. N 27° E .. 70 links ..

Marked "1/4 S NBT"

12" W. Pine .. S 13° E .. 92 links ..

Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner.

Found two cedar posts set by unknown surveyor. Found bottom of two white pine stumps in proper position, N 33° E 10 links and S 61° W 13 links.

Evidence of use by several old blases and signature on trees at this location and a brushed line running east.

1/4 Corner found by C. Limpert, District Forester.

Location poster placed on road 8 chs. east of 1/4 Corner and on road 6 chs. south of 1/4 Corner.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

DATE 4/23/57