

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Menominee

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>35</u> N. S., R. <u>29</u> E. W.	<u>M-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>35</u> N. S., R. <u>29</u> E. W.	<u>7, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- M-12 East $\frac{1}{4}$ corner - Sec. 36; wood post - Sp. Pine 16 - S20°W - 37 lks.; Sp. Pine 10 - N44°E - 17 lks.
 - 7 N. 1/16 corner on east section line - Sec. 36; not previously established.
 - 14 S. 1/16 corner on the East line of Sec. 36; not previously established.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- M-12 Set on line between the N.E. and S.E. section corners and in line with an old fence east (cor. falls in approx. centerline of N-S Co. Rd.). This position makes the north $\frac{1}{2}$ mile 2621.96' but it does fit the G.L.O. swamp calls in the north $\frac{1}{2}$ mile which a prop. position would not. Therefore, I believe the fence is the best evidence of the original $\frac{1}{4}$ corner position. The south $\frac{1}{2}$ mile measures 2737.61'.
 - 7 Set M.P.O.L. between the N.E. Section corner and the E $\frac{1}{4}$ corner of Sec. 36.
 - 14 Set M.P.O.L. between the E $\frac{1}{4}$ corner and the S.E. section corner of Sec. 36.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- M-12 1" pipe, 4" aluminum cap buried in road; 11" Oak (tw. top) - S78°E - 28.5'; 11" J. Pine - S45°E - 41.7'; 12" Oak - S41°W - 30.0'; 8" Oak - N35°W - 34.1'.
 - 7 1" pipe, 4" aluminum cap; 10" Bl. Oak - S59°W - 57.9'; 10" Bl. Oak - N21°W - 35.2'; 4" J. Pine - N9°E - 30.6'; 10" Bl. Oak - S23°E - 6.1'.
 - 14 1" pipe, 4" aluminum cap buried in road; 16" R. Pine - S14°W - 81.9'; 16" Oak - S66°E - 38.9'; 8" Oak - S80°W - 39.0'; 11" Oak - N35°E - 32.7'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 9-7-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

REGISTRATION NO. 21558