

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 35 N. S., R. 29 E. W.	L-4, M-5
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12/15/82, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-4 - Center 1/4 Cor. of Sec. 12; not previously established.
- M-5 - S.E. Sec. Cor. of Sec. 12; United Associates Inc. - 1961 set "T" iron with R.L.S. cap, 12" Maple - S60°E - 47.45'; 8" Maple - N20°E - 45.79'; 14" Oak - S45°W - 55.64'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-4 - Set at the intersection of the N-S and E-W 1/4 lines of Sec. 12.
- B-5 - Found "T" iron with R.L.S. cap set by United Associates Inc. of Cheboygan Michigan in 1961. Points of two old wood posts beside "T" Iron United Assoc. N.E. N.B.T. live and completed headled over (now 15"). Both other N.B.T.s had been cut. Stumps in place but cut too low for blaze marks. Set D.N.R. Mon. tight against "T" Iron which is below ground surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-4 - 1" pipe, 4" aluminum cap; 7" Oak N64°W 24.7'; 5" Spruce N21°W 36.5'; 6" H. Maple S51°E 9.0'; 9" W. Birch S57°W 20.3'.
- M-5 - 1" pipe, 4" aluminum cap; 15" Maple N17°E 45.15'; 9" W. Oak N73°W 31.3'; 7" W. Oak S71°W 17.45'; 11" Maple N70°E 2.87'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____