

MENOMINEE

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLL- 11 35 N. 29 W. ING IN SECTION _____ , T. _____ S., R. _____ W.		9, 12, 13
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 5, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

## A. Description of original monument and accessories and/or subsequent restoration:

- 9 - E. 1/16 Cor. on the E-W 1/4 line of Sec. 11; not previously established by survey.
- 12 - S 1/16 Cor. of Sec. 11.
- 13 - S.E. 1/16 Cor. (Ctr. of the S.E. 1/4) of Sec. 11; not previously established.

## B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9 - Set at the intersection of a line westerly from the E. 1/4 Cor. of Sec. 11 parallel with the S. Sec. line and a line Northerly from the E. 1/16 Cor. on the S. Sec. line parallel with the E. Sec. line. Sec. 11 is a fractional Sec. with no North or West Sec. lines.
- 12 - Set at the intersection of a line Northerly from the South 1/4 Cor. of Sec. 11 parallel with the East Sec. line and a line Westerly from the S. 1/16 Cor. on the East Sec. line, parallel with the South Sec. line of Sec. 11. Sec. 11 is a fractional Sec. with no North or West Sec. lines.
- 13 - Set at the computed Ctr. of the S.E. 1/4 of Sec. 11 by closed traverse. Sec. 11 is a fractional Sec. with no N. or W. Sec. line. 1/16 lines were set parallel to the East & South Sec. lines.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 - D.N.R. Mon.; 8" Oak - N20°E - 15.1'; 10" Oak - S83°E - 20.7'; 7" Oak - S16°E - 21.1'; 9" Oak - S75°W - 6.35'; 1 1/2" Angle Iron - N31°E - 16.4'.
- 12 - D.N.R. Mon.; 8" Oak - N62°E - 78.5'; 5" Oak - S72°E - 63.6'; 5" Oak - S31°W - 85.0'; 10" Oak - N66°W - 54.6'.
- 13 - D.N.R. Mon.; 13" W. Pine - N28°E - 62.8'; 10" R. Pine - N68°E - 57.0'; 6" J. Pine - S31°E - 10.6'; 7" J. Pine - S62°W - 28.1'.

SIGNED BY

*David B. Babbitt*

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)